

FEB. 12-14, 2019 | INDIANAPOLIS, IN

REVYOUR-ENGINES!



Protecting Our Waterways

The DigIndy Tunnel Program

November 12, 2019

Presentation by:

Michael Miller, PE – Construction Manager, Citizens Energy Group





Presentation Overview

- Combined and Separated Sewer Systems History
- Combined Sewer Overflow (CSO) Regulations
- Indianapolis' CSO Problem
- Indianapolis' Consent Decree / Long Term Control Plan Solution
- Geotechnical Program
- Dig Indy Tunnel System Update







The Problem: Indy's Combined Sewer Overflows







Combined Sewer Systems

Regulations:

- Clean Water Act (1972)
- Combined Sewer Overflow Policy (1994)
 & Minimum Controls Policy (1995)
- Financial Capability Guidance (1997)
- Water Quality Standards Guidance (2001)

Challenges:

- Significant capital costs for compliance
- CSO communities have higher wastewater rates
- Low income affordability
- Uncertain closure with U.S. EPA


Solutions & Benefits:

- Consent Decree (CD):
 - Agreement between City of Indianapolis, Citizens, U.S EPA and IDEM (2005)
 - All parties agreed that the LTCP process, per CSO Policy and Indiana law, was followed
- Benefits: Cleaner waterways, public health/recreation and development along waterways









Indy's Combined Sewer Overflows


- CSO Discharge Points (134)
- CSO Discharge Area (55 square miles)
- CSO Discharge Locations
 - White River Fall Creek
 - Pogues Run Pleasant Run
 - Eagle Creek
- CSO Frequency:
 - 60+/- times in a typical year
- CSO Discharge Volumes:
 - (Historically) ~5-6 billion gallons typical year
 - (Currently) DRTC & Eagle Creek Deep Tunnel are now capturing up to 1 billion gallons more raw sewage per year



We Are Not Alone



Over 100 Indiana Cities / Towns




Close to 800 U.S. Cities





Sustainable Solutions – Indy's CSO LTCP Overview


- Multi-Faceted CSO Long Term Control Plan:
 - Using Existing System Capacity
 - Expanding / Upgrading Advanced Wastewater Treatment Plants
 - Constructing New Storage and Conveyance








Overview of the DigIndy System



- Six deep rock tunnel segments
- 28 miles of deep rock tunnel
- 250 feet deep
- 20-foot bore
- 12-inch concrete liner
- 18-foot finished tunnel
- 270+ million gallons
- 13 years to construct
- Completed by 2025






Deep Tunnel Components





Consent Decree Milestones



- 12/31/2017 Deep Rock Tunnel Connector ✓
- 12/31/2017 − DRTC Pump Station ✓
- 12/31/2018 Eagle Creek Deep Tunnel ✓
- 12/31/2021 White River Tunnel
- 12/31/2021 Lower Pogues Run Tunnel
- 12/31/2021 Upper Pogues Run CSO Abatement
- 12/31/2025 Fall Creek Tunnel
- 12/31/2025 Pleasant Run Tunnel



Geotechnical Program Summary



Geotechnical Investigations



- Over 350 borings drilled up to 300 feet below the ground surface
- Vertical and inclined deep rock borings performed
- Piezometers and cluster monitoring wells set in vertical borings
- Sampling and testing of physical rock and soil characteristics
- Soil and groundwater environmental screening and sampling
- Hydraulic packer testing of bedrock permeability





Summary of Geotechnical Findings


- Rock Quality Designation (RQD) indicates bedrock is sound and relatively consistent, and not heavily fractured
- Unconfined Compressive Strength (UCS) averaged 9,000 to 10,000 pounds per square inch (psi)
- Tunneling-Related Rock Testing
 - Drilling Rate Index High to Extremely High (66 to 82)
 - Bit Wear Index Very Low to Extremely Low (6 to 12)







Illustrative Representation of Indianapolis' Geology




















Good Press!!!




















Deep Tunnel System Project Locations








Fall Creek Drop Shaft FC-06
























How deep is "Deep"?







DRTC Pump Station

- Construction Start April 2014
- Operation December 2017
- Current Construction Costs ~\$75M












DRTC Pump Station Cavern

- 100 feet long
- 60 feet wide
- 75 feet high
- Domed Arch Ceiling
- 700+ Rock Bolts
- 90+ Blasts to Excavate







Pump Station Elevator and Stair Tower

Finished Floor to Cavern Floor

- 266.83 feet
- 22-1/2 flights of stairs
- 495 individual steps
- 3 safety breathing equipment cabinets



DEEP TUNNEL SYSTEM FLOW DIRECTION

FALL CREEK DEEP TUNNEL

- 3.8 miles of 18-foot finished diameter tunnel
 13 drop shafts
- 4,400 feet of 24-inch to 108-inch diameter consolidation sewers

WHITE RIVER DEEP TUNNEL

- 5.8 miles of 18-foot finished diameter tunnel
- 7 drop shafts
- 4,800 feet of 42-inch to 108-inch diameter consolidation sewers

LOWER POGUES RUN DEEP TUNNEL

- 1.8 miles of 18-foot finished diameter tunnel
- 3 drop shafts
- 1,400 feet of 72-inch to 144-inch diameter consolidation sewers

PLEASANT RUN DEEP TUNNEL

- 7.3 miles of 18-foot finished diameter tunnel
- · 10 drop shafts
- 19,600 feet of 24-inch to 72-inch diameter consolidation sewers

EAGLE CREEK DEEP TUNNEL

- 1.7 miles of 18-foot finished diameter tunnel
- 1 drop shaft
- 2,800 feet of 48-inch diameter consolidation sewers

DEEP ROCK TUNNEL CONNECTOR AND PUMP STATION

- 7.6 miles of 18-foot finished diameter tunnel to Southport AWTP
- 3 drop shafts
- . 90 mgd tunnel pump station at Southport AWTP

Deep Rock Tunnel Connector







The Deep Rock Tunnel Connector & Eagle Creek Deep Tunnel

- First two legs of Citizens' 28-mile deep tunnel system
- 9.6 miles long
- 250 feet deep
- 20´bore diameter
- 12´´ thick concrete liner
- 18´ finished diameter
- \$220,000,000
- Construction complete,
 December 2017








DRTC – TBM Fun Facts

- 16 trailing gear decks
- 39 disc cutters (19" dia.) 280 lbs each
- Cutter head 92.5 tons
- Entire TBM 450 tons
- Eight (8) 450hp electric motors
- Cutter head turns at ~ 8rpm
- Cutter head torque 2,405,737 ft-lbs
- Gripper pads exert up to 7M lbs of force against the rock
- Cutter head exert up to 3M lbs of thrust at the face
- One foot of mined rock = approx. 20 yd³ of rock spoils










DRTC Launch Shaft / Mining Shaft











Launch Shaft







DRTC - Mined Tunnel







DEEP TUNNEL SYSTEM FLOW DIRECTION

FALL CREEK DEEP TUNNEL

- · 3.8 miles of 18-foot finished diameter tunnel
- . 4,400 feet of 24-inch to 108-inch diameter consolidation sewers

WHITE RIVER DEEP TUNNEL

- . 5.8 miles of 18-foot finished diameter tunnel
- · 7 drop shafts
- . 4,800 feet of 42-inch to 108-inch diameter consolidation sewers

LOWER POGUES RUN DEEP TUNNEL

- . 1.8 miles of 18-foot finished diameter tunnel
- . 1,400 feet of 72-inch to 144-inch diameter consolidation sewers

PLEASANT RUN DEEP TUNNEL

- 7.3 miles of 18-foot finished diameter tunnel
- 10 drop shafts
- 19,600 feet of 24-inch to 72-inch diameter consolidation sewers

EAGLE CREEK DEEP TUNNEL

- . 1.7 miles of 18-foot finished diameter tunnel
- . 2,800 feet of 48-inch diameter consolidation

DEEP ROCK TUNNEL CONNECTOR AND PUMP STATION

- 7.6 miles of 18-foot finished diameter tunnel to Southport AWTP
- · 3 drop shafts
- . 90 mgd tunnel pump station at Southport AWTP

Eagle Creek Tunnel







Eagle Creek Bifurcation







Unique Spoils








DRTC – TBM World Records


- Most Feet Mined One Day 409.89 feet
- Most Feet Mined One Week
 1,690.04 feet
- Most Feet Mined One Month
 5,755.15 feet







DRTC - Break Through







Concrete Lining - Formwork







DRTC Completed Tunnel










What's Next?





Two Down – Four to Go

- White River Tunnel 2021
- Lower Pogues Run Tunnel 2021
- Fall Creek Tunnel 2025
- Pleasant Run Tunnel 2025





White River & Lower Pogues Run

- 3rd and 4th legs of DigIndy system
- 7.8 miles feet of rock tunnel
- Construction began September 2016
- First segment of White River Tunnel and all Lower Pogues Run tunnel mining is complete
- \$200,000,000 contract value
- December 31, 2021









Acknowledgements

- Deep Rock Tunnel Connector & Pump Station and Eagle Creek Deep Tunnel
 - Designer AECOM
 - Construction Administrator AECOM
 - Tunnel Contractor Shea Kiewit JV
 - Pump Station Contractor Renda Southland JV
- White River, Lower Pogues Run, Fall Creek and Pleasant Run Tunnels
 - Designer Black & Veatch
 - Construction Administrator AECOM
 - Tunnel Contractor Shea Kiewit JV
 - Consolidation Sewer Contractor(s) TBD

